

BILL OF QUANTITIES

Project No. 21CW-GSC-006
Name of Project: CONSTRUCTION OF FLOODWAY AT CONEL-UDAGRE ROAD, PUROK NAVAL ROAD-732 TO LAGAO CONEL RD., BRGY. SAN ISIDRO, GENERAL SANTOS CITY
Location : BRGY. SAN ISIDRO, GENERAL SANTOS CITY
Duration : 175 CD
ABC : 9,046,770.78
Category : Small B

BID SCHEDULE

ITEM NO.	ESTIMATED QUANTITY	UNIT	WORK DESCRIPTION W/ UNIT BID PRICES WRITTEN IN WORDS	UNIT PRICE	AMOUNT OF BID
PART B			OTHER REQUIREMENTS		
B.5	2.00	each	Project Billboard / Signboard		
B.7	1.00	lumpsum	Construction Safety and Health Program		
B.8	1.00	lumpsum	Road Works Safety and Traffic Management (Layout 7, Case 2)		
B.9	1.00	lumpsum	Mobilization/Demobilization		
PART C			EARTHWORK		
100(3)a2	15.00	each	Individual Removal of Trees, 301-500 mm. dia., Small (For Replacement of Seedlings 1:100)		
101(4)a1	6.00	In.m.	Removal of Actual Structures/Obstruction (610 mm dia. RCPC)		
101(4)a3	5.00	In.m.	Removal of Actual Structures/Obstruction (910 mm dia. RCPC)		
101(6)a	169.42	cu.m.	Removal of Structures and Obstruction (Concrete Structures)		
102(2)	811.85	cu.m.	Surplus Common Excavation		
103(1)a	1047.55	cu.m.	Structure Excavation (Structure Excavation (Common Soil)		
103(6)a	47.24	cu.m.	Pipe culverts and drain excavation (Common Soil)		
104(1)a	249.57	cu.m.	Embankment from Roadway Excavation, Common Soil		
105(1)a	1370.23	sq.m.	Subgrade Preparation (Common Material)		
PART D			SUBBASE AND SUBBASE COURSE		

201(1)	274.05	cu.m.	Aggregate Base Course		
PART E			SURFACE COURSES		
311(1)c1	1166.55	sq.m.	PCC Pavement (Plain) - Conventional Method, 230 mm thick		
PART F			BRIDGE CONSTRUCTION		
404(1)a	16474.47	kg	Reinforcing Steel Bar, Grade 40		
405(1)a1.1	175.15	cu.m.	Structural Concrete Class A		
PART G			DRAINAGE AND SLOPE PROTECTION		
500(1)a1	25.00	ln.m.	Pipe Culverts, 610mm dia. (24" dia.)		
502(3)	5.00	ea.	Catch Basin, (Concrete), (with 3" dia. PVC pipe as drains)		
502(2)a1	5.00	ea.	Inlet, (Concrete, with 3" dia. PVC pipe as drains)		
508(1)	4.98	cu.m.	Hand Laid Rock Embankment		
PART H			MISCELLANEOUS STRUCTURES		
600(4)	304.00	ln.m.	Concrete Curb and Gutter (RIGHT SIDE)		
611(1)	708.00	ea.	Trees Furnishing (Seedlings)		
612(1)	99.80	sq.m.	Reflectorized Thermoplastic Pavement Markings (White)		
PART I			MATERIALS DETAILS		
704(1)	7600.00	each	Masonry Units (With Finishing)		

(In Figures)

TOTAL AMOUNT OF BID:

(In Words)