

# BILL OF QUANTITIES

**Project No.** 21CW-GSC-008  
**Name of Project:** CONSTRUCTION OF DRAINAGE AT NUÑEZ ST., BARANGAY SAN ISIDRO, GENERAL SANTOS CITY  
**Location :** BARANGAY SAN ISIDRO, GENERAL SANTOS CITY  
**Duration :** 170 CD  
**ABC :** 13,472,619.01  
**Category :** Small B

## BID SCHEDULE

ITEM NO.	ESTIMATED QUANTITY	UNIT	WORK DESCRIPTION W/ UNIT BID PRICES WRITTEN IN WORDS	UNIT PRICE	AMOUNT OF BID
<b>PART B</b>			<b>OTHER GENERAL REQUIREMENTS</b>		
B.5	2.00	each	Project Billboard/ Signboard		
B.7	1.00	lumpsum	Construction Safety and Health Program		
B.8	1.00	lumpsum	Road Works Safety and Traffic Management (Layout 7, Case 2)		
B.9	1.00	lumpsum	Mobilization/Demobilization		
<b>PART C</b>			<b>EARTHWORK</b>		
100(3)a1	20.00	each	Individual Removal of Trees, 150-300 mm. dia., Small (For Replacement of Seedlings 1:100)		
101(3)b1	255.47	sq.m.	Removal of Actual Structures/Obstruction (0.15m thk-PCCP Unreinforced)		
101(3)b2	38.81	sq.m.	Removal of Actual Structures/Obstruction (0.20m thk-PCCP Unreinforced)		
101(6)a	0.14	cu.m.	Removal of Structures and Obstruction (Concrete Structures)		
102(2)	243.21	cu.m.	Surplus Common Excavation		
103(6)a	2555.12	cu.m.	Pipe culverts and drain excavation (Common Soil)		
104(2)a	1467.93	cu.m.	Embankment from borrow (Common Soil)		
105(1)a	1629.80	sq.m.	Subgrade Preparation (Common Material)		
<b>PART D</b>			<b>SUBBASE AND BASE COURSE</b>		
201(1)	325.96	cu.m.	Aggregate Base Course		

<b>PART E</b>			<b>SURFACE COURSES</b>		
311(1)b1	979.92	sq.m.	PCC Pavement (Plain) - Conventional Method, 200 mm thick (with retrofitting)		
<b>PART G</b>			<b>DRAINAGE AND SLOPE PROTECTION STRUCTURES</b>		
500(1)a3	840.00	ln.m.	Pipe Culverts, 910mm dia. (36" dia.)		
502(1)a3	29.00	ea.	Manhole, 910mm dia. (Concrete), (with 3" dia. PVC pipe as drains)		
502(2)a1	30.00	ea.	Inlet, (Concrete, with 3" dia. PVC pipe as drains)		
502(3)a	30.00	ea.	Catch Basin for 36 in RCPC		
<b>PART H</b>			<b>MISCELLANEOUS STRUCTURES</b>		
600(4)	790.00	ln.m.	Concrete Curb and Gutter		
611(1)	2000.00	ea.	Trees Furnishing (Seedlings)		
612(1)	464.22	sq.m.	Reflectorized Thermoplastic Pavement Markings (White)		

(In Figures)

TOTAL AMOUNT OF BID:

---

(In Words)