

# BILL OF QUANTITIES

**Project No.** 21CW-GSC-010  
**Name of Project:** ROAD CONCRETING AT PUROK 2, BARANGAY TINAGACAN,  
 GENERAL SANTOS CITY (FROM NATIONAL HIGHWAY TO PUBLIC  
 MARKET SITE)  
**Location :** BARANGAY TINAGACAN, GENERAL SANTOS  
**Duration :** 45 CD  
**ABC :** 2,456,462.26  
**Category :** Small B

## BID SCHEDULE

ITEM NO.	ESTIMATED QUANTITY	UNIT	WORK DESCRIPTION W/ UNIT BID PRICES WRITTEN IN WORDS	UNIT PRICE	AMOUNT OF BID
<b>PART B</b>			<b>OTHER GENERAL REQUIREMENTS</b>		
B.5	2.00	each	Project Billboard/ Signboard		
B.7	1.00	lumpsum	Construction Safety and Health Program		
B.8	1.00	lumpsum	Road Works Safety and Traffic Management (Layout 7, Case 1)		
<b>PART C</b>			<b>EARTHWORK</b>		
102(2)	579.46	cu.m.	Surplus Common Excavation		
105(1)a	1788.09	sq.m.	Subgrade Preparation (Common Material)		
<b>PART D</b>			<b>SUBBASE AND BASE COURSE</b>		
201(1)	441.08	cu.m.	Aggregate Base Course		
<b>PART E</b>			<b>SURFACE COURSES</b>		
311(1)c1	1425.23	sq.m.	PCC Pavement (Plain) - Conventional Method, 230 mm thick (with retrofitting)		
<b>PART H</b>			<b>MISCELLANEOUS STRUCTURES</b>		
612(1)	50.28	sq.m.	Reflectorized Thermoplastic Pavement Markings (White)		

(In Figures)

TOTAL AMOUNT OF BID:

---

(In Words)