

BILL OF QUANTITIES

Project No. 21CW-GSC-013
Name of Project: IMPROVEMENT OF ROAD SECTION AT F. SANTOS, BRGY. SAN ISIDRO, GENERAL SANTOS CITY (ADDITIONAL APPROPRIATION)
Location : BRGY. SAN ISIDRO, GENERAL SANTOS CITY
Duration : 75 CD
ABC : 5,099,998.78
Category : Small B

BID SCHEDULE

ITEM NO.	ESTIMATED QUANTITY	UNIT	WORK DESCRIPTION W/ UNIT BID PRICES WRITTEN IN WORDS	UNIT PRICE	AMOUNT OF BID
PART B			OTHER REQUIREMENTS		
B.5	2.00	each	Project Billboard / Signboard		
B.7	1.00	lumpsum	Construction Safety and Health Program		
B.8	1.00	lumpsum	Road Works Safety and Traffic Management (Layout 7, Case 2)		
B.9	1.00	lumpsum	Mobilization/Demobilization		
PART C			EARTHWORK		
101(3)b2	50.30	sq.m.	Removal of Actual Structures/Obstruction (0.20m thk-PCCP Unreinforced)		
102(2)	2030.00	cu.m.	Surplus Common Excavation		
103(1)a	93.00	cu.m.	Structure Excavation (Common Soil)		
104(1)a	82.00	cu.m.	Embankment from Roadway Excavation, Common Soil		
105(1)a	3277.80	sq.m.	Construction Safety and Health Program		
PART D			SUBBASE AND BASE COURSE		
201(1)	867.00	cu.m.	Aggregate Base Course		
PART E			SURFACE COURSES		
311(1)c1	2361.50	sq.m.	PCC Pavement (Plain) - Conventional Method, 230 mm thick		
PART F			BRIDGE CONSTRUCTION		

401(5)	1.00	lumpsum	Pedestrian Railing		
404(1)a	3694.90	kg	Reinforcing Steel Bar, Grade 40		
405(1)a1	39.40	cu.m.	Structural Concrete Class A		
PART G			DRAINAGE AND SLOPE PROTECTION STRUCTURES		
508 (1)	10.00	cu.m.	Hand Laid Rock Embankment		

(In Figures)

TOTAL AMOUNT OF BID:

(In Words)